



DRAFT



# Nishi Gateway Project

## Sustainability Implementation Plan

September 2015



PREPARED FOR:  
City of Davis  
23 Russell Blvd Suite 2  
Davis, CA 95616



# Nishi Gateway Project

## Sustainability Implementation Plan

*Draft*

Prepared by



**Ascent Environmental, Inc.**

In collaboration with:

MIG  
Fehr & Peers  
Davis Energy Group  
Cunningham Engineering

**September 2015**



# Table of Contents

	<b>Page</b>
<b>1 INTRODUCTION.....</b>	<b>1-1</b>
1.1 Purpose.....	1-3
1.2 Guiding Principles and Goals .....	1-4
1.3 Sustainability Goals and Objectives.....	1-5
1.4 Sustainability Plan Implementation.....	1-8
1.5 Comparison with Other “Green” Rating Systems/Programs.....	1-10
<b>2 NISHI GATEWAY PROJECT OVERVIEW .....</b>	<b>2-1</b>
2.1 Nishi Property .....	2-1
2.2 West Olive Drive.....	2-9
2.3 Entitlements and Subsequent Actions.....	2-9
2.4 Goals and Objectives.....	2-10
2.5 Implementing Actions.....	2-11
2.6 Evaluation and Monitoring .....	2-15
<b>3 TRANSPORTATION .....</b>	<b>3-1</b>
3.1 Goals and Objectives.....	3-3
3.2 Implementing Actions.....	3-4
3.3 Evaluation and Monitoring .....	3-21
<b>4 ENERGY .....</b>	<b>4-1</b>
4.1 Goals and Objectives.....	4-2
4.2 Implementing Actions.....	4-3
4.3 Evaluation and Monitoring .....	4-19
<b>5 WATER.....</b>	<b>5-1</b>
5.1 Goals and Objectives.....	5-1
5.2 Implementing Actions.....	5-2
5.3 Evaluation and Monitoring .....	5-18
<b>6 OPEN SPACE AND PARKS.....</b>	<b>6-1</b>
6.1 Goals and Objectives.....	6-3
6.2 Implementing Actions.....	6-4
6.3 Evaluation and Monitoring .....	6-15

## Appendices

A	Green Rating Systems	
B	Transportation Demand Management Study	
C	Zero Net Energy (ZNE) Feasibility Study	
D	Preliminary Site Water, Sewer and Drainage Infrastructure Concepts Study	
E	Open Space and Parks Technical Study	
F	Implementation Plan Summary	

## Figures

Figure 2-1	Draft Site Plan .....	2-3
Figure 3-1	Existing Bicycle Infrastructure .....	3-11
Figure 3-2	Existing Transit Infrastructure .....	3-13
Figure 3-3	TDM Plan Monitoring Process.....	3-24
Figure 4-1	Sun Angle during Summer and Winter.....	4-4
Figure 4-2	Shading on West Facing Glass .....	4-4
Figure 4-3	Left Image: Rigid Insulation at the Wall Exterior. Right Image: Double Stud Wall.....	4-5
Figure 4-4	Ground Source Heat Pump with Community Loop.....	4-5
Figure 4-5	Nighttime Ventilation Cooling (AHU = Air Handler Unit).....	4-6
Figure 4-6	Central Domestic Hot Water System .....	4-7
Figure 4-7	ecobee Remote Communicating Thermostat and Honeywell Home Energy Use Dashboard.....	4-9
Figure 4-8	Indirect/Direct Evaporative Cooling .....	4-10
Figure 4-9	Heat or Energy Recovery Ventilator .....	4-11
Figure 4-10	Example of Light Shelves in Commercial Building.....	4-11
Figure 4-11	LED Outdoor Fixture.....	4-13
Figure 4-12	Solar Pool Heating .....	4-14
Figure 4-13	Maximizing Building Rooftop Area for PV .....	4-15
Figure 4-14	System Installed over Rooftop HVAC Equipment .....	4-16
Figure 4-15	Sawtooth PV Installation.....	4-16
Figure 4-16	Parking Lot Shading PV System Installations.....	4-17
Figure 5-1	Conceptual Domestic Water System, Option A.....	5-3
Figure 5-2	Conceptual Domestic Water System, Option B.....	5-4
Figure 5-3	Conceptual Non-Potable Water System.....	5-9
Figure 5-4	Sanitary Sewer Collection System Concept, Option A.....	5-13
Figure 5-5	Sanitary Sewer Collection System Concept, Option B1 .....	5-14
Figure 5-6	Sanitary Sewer Collection System Concept, Option B2 .....	5-15
Figure 6-1	Open Space and Parks Plan.....	6-2

**Tables**

Table 2-1 Nishi Development Land Use and Site Program Summary..... 2-4

Table 2-2 Annual GHG Emissions Scenarios for the Nishi Development.....2-17

Table 2-3 Performance Metrics .....2-18

  

Table 3-1 Estimated Project Trips, without TDM Program..... 3-8

Table 3-2 Estimated VMT Reductions from Primary Actions .....3-22

Table 3-3 Estimated VMT Reductions from Supporting Actions.....3-22

  

Table 4-1 Impact of Projected Energy Savings for the Nishi Development Relative  
to a Business-as-Usual Scenario .....4-20

Table 4-2 Solar PV Energy Generation and ZNE Evaluation.....4-21

Table 4-3 Energy Performance Metrics .....4-24

  

Table 5-1 Nishi Development: Daily Water Demand by Land Use ..... 5-5

Table 5-2A Inside-Use Reduction .....5-10

Table 5-2B Inside-Use Volume Reduction .....5-10

Table 5-3A Outside-Use Potable Water Reduction .....5-11

Table 5-3B Outside-Use Potable Water Volume Reduction .....5-11

Table 5-4 Water Performance Metrics.....5-20

  

Table 6-1 Site Plan Parks and Open Space Evaluation .....6-15

Table 6-2 Parks and Open Space Performance Metrics.....6-16

# Acronyms and Abbreviations

afy	acre-feet/year
AVR	average vehicle ridership
BAU	business-as-usual
CAPCOA	California Air Pollution Control Officers Association
CC&Rs	Covenants, Conditions, and Restrictions
CCT	correlated color temperature
City	City of Davis
CLTC	UC Davis California Lighting Technology Center
CRI	color rendering index
DHW	domestic hot water
EMS	energy management system
EUI	Energy Use Intensity
GHG	greenhouse gas
HEF	high-efficiency fixture
HVAC	heating, ventilation, and air conditioning
I-80	Interstate 80
LED	light emitting diode
LID	low-impact development
mgy	million gallons per year
MTCO <sub>2</sub> e	metric tons of carbon dioxide equivalent
NREL	National Renewable Energy Lab
PV	photovoltaic
SACOG	Sacramento Area Council of Governments
sf	square feet
SIP	Sustainability Implementation Plan
SOV	single-occupant vehicle
TDM	Transportation Demand Management
TMP	transportation management plan
UC Davis	University of California Davis
UHEF	ultra-high-efficiency fixture
UPRR	Union Pacific Railroad
VHEF	very-high-efficiency fixture
VMT	vehicle miles traveled
WOD	West Olive Drive
WSA	water supply assessment
WWTP	wastewater treatment plant
ZNE	zero net energy
ZNE-TDV	Zero Net Energy – Time Dependent Valuation